

CLIENT	PROJECT
Edgemont Floors Inc.	4725 The Glen, West Vancouver, BC V7S 3C3
Attention: Iman — Chief Executive Officer	Basement room expansion — under-deck enclosure

Project Description

Removal of the existing basement exterior wall (including the sliding glass door) and construction of three new exterior walls under the deck (front wall ~19 ft with two double-pane windows and one entry door; two side walls ~9.5 ft each); conversion of the existing deck into the room's roof, including salvage removal of the composite decking, sloped sheathing, a walkable waterproof membrane, and re-installation of decking and railings; thermal insulation of walls and roof; new foundations; stucco exterior matched to the building; complete electrical, heating/ventilation and interior finishes. Added floor area approximately 180 sq ft. All work per BC Building Code 2024.

Itemized Pricing

#	Item (material + labour)	Price
1	Mobilization, site protection, disposal bins and dump fees	\$2,500
2	Demolition of existing exterior wall (including sliding glass door)	\$3,500
3	Salvage removal of composite decking and railing sections	\$2,800
4	Concrete slab cutting, excavation and base grading	\$3,200
5	Concrete footings and stem walls, 38 lf (rebar, forms, pump, pour)	\$9,500
6	Slab infill + under-slab rigid insulation + 6-mil poly + radon rough-in	\$4,200
7	Perimeter drainage and damp-proofing	\$2,800
8	Framing of three 2x6 exterior walls with headers and seismic hardware	\$7,500
9	Deck joist reinforcement and blocking	\$3,200
10	Sloped roof sheathing over deck joists	\$2,900
11	Walkable waterproof membrane (60-mil vinyl or 2-ply SBS) with full flashings	\$5,500
12	Re-lay composite decking on sleepers and reinstate railings	\$3,400
13	Supply and install 2 top-tier double-pane Low-E argon windows	\$2,900
14	Supply and install 1 quality insulated exterior entry door	\$2,800

15	Wall insulation to R-22 effective + complete air sealing	\$2,600
16	Roof insulation from below: R-28 batt + poly vapour barrier	\$1,800
17	3-coat stucco with rainscreen and WRB, matched to existing exterior	\$9,000
18	Soffit, fascia and finishing flashings	\$1,900
19	Electrical by licensed electrician: circuits, receptacles, pot lights, smoke/CO	\$5,500
20	Heating and ventilation: electric baseboards, thermostat, ventilation fan	\$2,200
21	Drywall, taping (tape and mud) and complete painting	\$4,200
22	Interior flooring, baseboards and trim	\$3,600
23	Equipment rentals: mini excavator, compactor, scaffolding	\$2,000
24	Site supervision and project management	\$4,500
	Subtotal	\$94,000
	GST 5%	\$4,700
	Total contract amount	\$98,700

Project Duration

The project duration is **45 working days** (weekends and statutory holidays are not counted). Should unforeseen circumstances arise – including adverse weather, concealed structural or soil conditions, or material supply delays – this duration may be extended by up to **two weeks**, with written notice to the Client.

Important recommendation regarding permits: As the majority of this project consists of exterior work (exterior walls, cladding and roof), Pacific Custom Builders Ltd. **strongly recommends** that the building permit process be completed before work begins. Should the project be cancelled at any stage due to a municipal Stop-Work Order, the Contractor will issue a final and conclusive invoice for all labour costs incurred, all materials purchased or ordered and paid for, plus **20% of the total contract amount**, and the Client shall be obligated to pay it.

Terms and Conditions

- Payment schedule:** 10% on signing; 25% on completion of foundations; 25% on completion of framing and membrane; 25% on completion of exterior and insulation; 15% on final handover. Invoices are payable within 7 days; overdue amounts bear interest at 2% per month.
- Change orders:** Any change to the scope of work shall be made only by a written change order signed by both parties, with corresponding price and schedule adjustment.

3. **Concealed conditions:** Unforeseeable structural, soil, moisture or hidden-services conditions within the existing wall/slab are excluded from this price and will be handled by written change order.
4. **Composite decking:** Priced on the basis that the existing boards are salvaged and re-laid. If boards are damaged during removal, supplying new boards adds approximately \$4,500 to the contract, subject to the Client's written approval.
5. **Exterior match:** Stucco colour and texture will be matched to the existing exterior as closely as practicable; given the age of the current finish, an exact colour match cannot be guaranteed.
6. **Warranty:** 2-year workmanship warranty from the date of handover; material warranties (windows, door, membrane, etc.) per manufacturer.
7. **Insurance:** The Contractor carries commercial general liability insurance and WorkSafeBC coverage for all site personnel.
8. **Client responsibilities:** Providing site access, construction water and power, and clearing furniture from the work area before start.
9. **Exclusions:** Permit and engineering fees, furniture and decor, landscaping and garden restoration beyond the work area, and any work not listed in the itemized table above.
10. **Cancellation by Client:** If cancelled without Contractor default, the cost of work performed and materials purchased/ordered plus 10% of the remaining contract amount is payable.
11. **Dispute resolution:** This agreement is governed by the laws of British Columbia; disputes will be resolved first by negotiation and then by arbitration in Vancouver.

Pacific Custom Builders Ltd.

Authorized signatory — Per:

Date:

Edgemont Floors Inc.

Iman — Chief Executive Officer

Date: