



ESTIMATE No: PCB-2026-081

Date: August 13, 2026

Valid: 30 days

PACIFIC CUSTOM BUILDERS LTD. — GENERAL CONTRACTOR — COQUITLAM, BC
Tel: 604-721-9610 • Majid@pcb ltd.ca • www.pcb ltd.ca

CLIENT

Edgemont Floors Inc.

Attention: Iman — Chief Executive Officer

PROJECT

4725 The Glen, West Vancouver, BC V7S 3C3

Basement room expansion — under-deck enclosure

Project Description

Removal of the existing basement exterior wall (including the sliding glass door) and construction of three new exterior walls under the deck (front wall ~19 ft with two double-pane windows and one entry door; two side walls ~9.5 ft each); conversion of the existing deck into the room's roof, including salvage removal of the composite decking, sloped sheathing, a walkable waterproof membrane, and re-installation of decking and railings; thermal insulation of walls and roof; new foundations; stucco exterior matched to the building; complete electrical, heating/ventilation and interior finishes. Added floor area approximately 180 sq ft. All work per BC Building Code 2024.

Itemized Pricing

#	Item (material + labour)	BCBC 2024 ref.	Price
1	Mobilization, site protection, disposal bins and dump fees	Part 8	\$2,500
2	Demolition of existing exterior wall (including sliding glass door)	Part 8	\$3,500
3	Salvage removal of composite decking and railing sections	Part 8	\$2,800
4	Existing slab cutting, excavation to below frost depth, base grading	9.12.1, 9.12.2.2	\$3,200
5	Concrete footings and stem walls under all three walls, 38 lf (rebar, forms, pump, pour; min 20 MPa concrete, code-compliant plate anchor bolts)	9.15, 9.3.1, 9.23.6	\$9,500
6	Slab infill + granular layer + under-slab rigid insulation + 6-mil poly + radon rough-in	9.16, 9.13.4, 9.25.4	\$4,200
7	Foundation perimeter drainage and damp-proofing	9.14, 9.13.2	\$2,800
8	Framing of three 2x6 exterior walls with headers, PT plates on concrete, and seismic braced wall panels	9.23, 9.23.13	\$7,500
9	Deck joist reinforcement and blocking for roof + deck loading	9.23.4, Part 4	\$3,200

10	Sloped roof sheathing over joists (minimum slope for membrane drainage)	9.23.16, 9.26.3	\$2,900
11	Standard-compliant walkable waterproof membrane (60-mil vinyl CGSB-37.54 or 2-ply SBS) with full flashings	9.26	\$5,500
12	Re-lay composite decking on sleepers and reinstate railings (guard height and loads per code)	9.8.8	\$3,400
13	Supply and install 2 top-tier double-pane Low-E argon windows (NAFS; USI ≤ 1.61)	9.7, 9.36.2.7	\$2,900
14	Supply and install 1 quality insulated exterior entry door (NAFS; USI per code)	9.7, 9.36.2.7	\$2,800
15	Wall insulation to R-22 effective + complete air sealing (exceeds code minimum)	9.36.2.6, 9.25	\$2,600
16	Roof insulation from below: R-28 batt + poly vapour barrier; vented space above insulation in every joist bay	9.36.2.6, 9.19, 9.25	\$1,800
17	3-coat stucco with rainscreen (≥10mm capillary break) and WRB, matched to existing	9.27.2.2, 9.28	\$9,000
18	Soffit, fascia, finishing flashings and continuous roof vents with insect screen	9.19, 9.26.4	\$1,900
19	Electrical by licensed electrician: circuits, receptacles (code spacing), pot lights, interconnected smoke and CO alarms	CEC-BC, 9.10.19, 9.32.3.9	\$5,500
20	Heating sized to code design capacity and mechanical ventilation of the new space	9.33, 9.32	\$2,200
21	Drywall, taping (tape and mud) and complete painting	9.29	\$4,200
22	Interior flooring, baseboards and trim	—	\$3,600
23	Equipment rentals: mini excavator, compactor, scaffolding	—	\$2,000
24	Site supervision and project management	—	\$4,500
Subtotal			\$94,000
GST 5%			\$4,700
Total contract amount			\$98,700

BC Building Code Compliance (BCBC 2024)

- **Foundations are mandatory:** exterior walls must bear on footings and foundations (Section 9.15) with bearing below the depth of frost penetration (9.12.2.2). Placing the walls on the existing patio slab is therefore not permitted, and items 4–7 are an inseparable part of the project.
- **Seismic:** West Vancouver is in a high seismic zone; wall bracing and connections are built per 9.23.13.

- **Batt-insulated roof joists:** the space above the insulation is ventilated in every joist bay (Section 9.19) via continuous vents at both ends of each bay; the poly vapour barrier is installed on the warm side (9.25.4).
- **Energy:** R-22 effective walls and windows/door at USI ≤ 1.61 meet or exceed Section 9.36 requirements.
- **Room height:** the ~9 ft ceiling is well above the Section 9.5 minimum.
- **Radon:** sub-slab rough-in per 9.13.4 (province-wide requirement in BCBC 2024).
- **Fire and life safety:** smoke alarms interconnected with the whole house (9.10.19) and CO alarm (9.32.3.9).

Project Duration

The project duration is **45 working days** (weekends and statutory holidays are not counted). Should unforeseen circumstances arise – including adverse weather, concealed structural or soil conditions, or material supply delays – this duration may be extended by up to **two weeks**, with written notice to the Client.

Important recommendation regarding permits: As the majority of this project consists of exterior work (exterior walls, cladding and roof), Pacific Custom Builders Ltd. **strongly recommends** that the building permit process be completed before work begins. Should the Client wish to obtain a permit, our company can – at a separate cost – carry out all structural design work, the required approvals, and the complete permit application process before the project starts.

Should the Client make the final decision to start and carry out the project without obtaining a permit, the risk of that decision rests directly with the Client, and should a municipal Stop-Work Order be encountered at any stage of the project, the responsibility for obtaining the permit shall rest with the Client. If the project shutdown due to municipal requirements continues for more than **30 working days**, the project shall be cancelled and all project costs, including materials and labour, plus **10% of the remaining balance of the total contract amount**, plus GST, shall be presented to the Client in a single invoice as the final invoice, and the Client shall be obligated to pay it in accordance with the invoice payment schedule set out in the contract. Any delay in payments shall bear late-payment interest at **2% per month (24% per annum)** from the due date, in line with prevailing construction industry practice and with the annual rate stated as required by the federal Interest Act.

Terms and Conditions

1. **Change orders:** Any change to the scope of work shall be made only by a written change order signed by both parties, with corresponding price and schedule adjustment.
2. **Concealed conditions:** Unforeseeable structural, soil, moisture or hidden-services conditions within the existing wall/slab are excluded from this price and will be handled by written change order.
3. **Composite decking:** Priced on the basis that the existing boards are salvaged and re-laid. If boards are damaged during removal, supplying new boards adds approximately \$4,500 to the contract, subject to the Client's written approval.

4. **Exterior match:** Stucco colour and texture will be matched to the existing exterior as closely as practicable; given the age of the current finish, an exact colour match cannot be guaranteed.
5. **Warranty:** 2-year workmanship warranty from the date of handover; material warranties (windows, door, membrane, etc.) per manufacturer.
6. **Insurance:** The Contractor carries commercial general liability insurance and WorkSafeBC coverage for all site personnel.
7. **Client responsibilities:** Providing site access, construction water and power, and clearing furniture from the work area before start.
8. **Exclusions:** Permit and engineering fees, furniture and decor, landscaping and garden restoration beyond the work area, and any work not listed in the itemized table above.
9. **Cancellation by Client:** If cancelled without Contractor default, the cost of work performed and materials purchased/ordered plus 10% of the remaining contract amount is payable.
10. **Dispute resolution:** This agreement is governed by the laws of British Columbia; disputes will be resolved first by negotiation and then by arbitration in Vancouver.

Pacific Custom Builders Ltd.

Prepared by — Authorized signatory

Date: August 13, 2026